LAYOUT PLAN (1:50)

NOTES

1). All works to be carried out in conformance with the local Authority regulations.
2). All dimensions are in millimetres unless otherwise indicated.

4). Depth of foundations to be determined on site.
5). 1000 gauge polythene damp proof membrane to be provided under ground floor slab.
6). Approved damp proof course (D. P. C) to be provided under ground floor walls.
7). Permanent air vents to be provided over all openings except over interior WC & Shower doors.

8). Approved anti-termite treatment to be performed before work is carried out.

9). All drainage pipes passing under building and driveways to be encased in 150mm thick concrete surround.

10). All retaining walls to have weep holes to S.E details

Revision.

Rev. No:	Details.	Date.

Drawing Title.

AS SHOWN

Job Title:

PROPOSED OFFICE PARTITIONING

Developer:

-

Client's sign.....

Archetypum Afrika
architects, project managers & planning consultants
P.O. BOX. 14531-00100
Tel No. 0706673310
www.archetypum-afrika.com

Architect:
E.J.O.Gono (A1003)

Signature.....Date.....

Drawn:	Checked:
K. MUIIRURI	E.J.O

Scales:	Date.
AS SHOWN	SEPT. 2017

Job No:	Drg. No:	Rev. No: